

GRANT COUNTY BOARD OF COMMISSIONERS

112 E. Guthrie – Room 104 – Courthouse
Medford, Oklahoma 73759
Courthouse Phone 580-395-2214 – Courthouse FAX 580-395-2603
Dessie Scott, Executive Assistant
grantcommissioners@gmail.com

Max L. Hess

District 1 Commissioner
Shop phone 580-594-2925
Shop fax 580-594-2926
Cell phone 580-541-4740

Cindy R. Bobbitt

District 2 Commissioner
Shop phone 580-395-2859
Shop fax 580-395-2972
Cell phone 580-541-8950

Steve Stinson

District 3 Commissioner
Shop phone 580-532-6499
Shop fax 580-532-6497
Cell phone 580-741-1044

INVITATION TO BID #17-2020 PHONE/FAX QUOTE

The Grant County Fair Board of Grant County, Oklahoma are taking quotes for a **“DRAINAGE PROJECT”** for the Grant County Expo Center located in Pond Creek, Oklahoma, as described in the **SPECIFICATION SHEET-#17-2020**. This quote is being solicited according to O.S., Title 61, §101-138–Construction project \$50,000 and under.

TOTAL BASE PROJECT QUOTE: \$ _____ Quote Expires: _____

ADDITIONAL OPTIONS: \$ _____ Quote Expires: _____

VENDOR: _____

ADDRESS: _____

CONTACT PHONE NUMBER: _____

EMAIL ADDRESS: _____

FED EMPLOYER ID# or SSN# _____

SIGNATURE: _____

QUALIFIED QUOTES MUST INCLUDE PROOF OF VENDOR LIABILITY INSURANCE OR A PERFORMANCE BOND.

Please email quote to cpratt@grant.okcounties.org or fax to 580-395-2086

“ATTN: BID #17-2020 – GC EXPO CENTER – DRAINAGE PROJECT”

QUOTES ARE DUE NO LATER THAN: Wednesday, August 19, 2020 @ 4:30 p.m.

For more information, please contact or Tim Winter, GC Fair Board Member, at 580-554-3906 or Cindy Pratt, Grant County Clerk, at 580-395-2274.

All quotes will be reviewed with possible acceptance or rejection on Monday, August 24, 2020, during the regular meeting of the Board of County Commissioners of Grant County, Oklahoma.

SPECIFICATIONS FOR
BID #17-2020
GRANT COUNTY EXPO CENTER
POND CREEK, OKLAHOMA
DRAINAGE PROJECT

EAST SIDE OF THE FRONT OF BUILDING STARTING AT THE 3RD DOWN SPOUT TO THE WEST, DIG A TRENCH APPROXIMATELY 47 FEET 6 INCHES EAST AND CONNECT THE REMAINING TWO DOWN SPOUTS. DIG UNDER SIDEWALK THEN BLADE GRAVEL BACK AND TRENCH APPROXIMATELY 118 FEET TO THE NORTH DITCH.

WEST SIDE OF THE FRONT OF THE BUILDING STARTING AT THE EAST DOWN SPOUT, THEN TRENCH 42 FEET 6 INCHES TO THE SIDEWALK AND CONNECT THE TWO OTHER DOWN SPOUTS. CONNECT THE ELECTRICAL CONDUIT INTO THE DITCH WITH DRAINPIPE. BLADE ROCK OFF AND DIG UNDER THE SIDEWALK. TRENCH 116 FEET NORTH TO THE DITCH BRINGING THE ELECTRICAL CONDUIT ABOVE GROUND.

THE GRANT COUNTY FAIR BOARD WILL PROVIDE THE FOLLOWING: 6 INCH PIPING

BIDDER WILL PROVIDE THE FOLLOWING: 90° FITTINGS, TEES, COUPLER, ELECTRICAL CONDUIT & FITTINGS.

EACH SIDE IS TO HAVE 6 INCH COVER OVER PIPE.

GRANT COUNTY FAIR BOARD WILL CONTACT OKIE DIG TO LOCATE ALL BURIED LINES.

AT DITCH CUT PIPE AT 45° AND CONCRETE 18 INCHES BY 18 INCHES. SQUARE 4 INCHES THICK AND FLUSH WITH GROUND.

ONE SIX INCH WATER MAIN KNOWN TO BE IN DITCH.